

**KARNATAKA VETERINARY, ANIMAL AND FISHERIES SCIENCES UNIVERSITY, BIDAR
COLLEGE OF FISHERIES, MANGALURU- 575002**

No.FCM/EB/RCC precast fencing pole/2021-22(10)

Date: 13/12/2021

Quotation Enquiry

**Sub: Quotation towards Providing and fixing RCC precast fencing pole near Fish farm at
College of Fisheries Mangalore-Reg.**


With reference to the above cited subject, sealed quotations are invited for following work. The quotation should reach the undersigned on or before 28/12/2021.

Please refer **Schedule B** for detailed work description.

Note:

- 1) Quotations received after last date and having description of the materials incomplete will not be entertained.
- 2) Quotations should be raised in favour of "**Dean, College of Fisheries, Mangaluru-575002**".
- 3) Write quotation reference number and quotation last date on sealed covers.
- 4) Rates should be quoted in Indian currency per unit.
- 5) Details of tax etc. should be mentioned separately.
- 6) Lowest quotation rate would be accepted.
- 7) The total amount for all the above items will considered for calculation and placing order is subjected to meeting all the above conditions.

Yours faithfully


Dean (Fisheries)
College of Fisheries
Mangaluru

Copy to:

- 1) Notice Board, College of Fisheries, Mangaluru
- 2) Notice Board, Technology Wing, Hoige Bazar.
- 3) Assistant Comptroller, COF, Mangaluru for kind information
- 4) College Website: www.cofm.edu.in

Schedule - B

Name of work :Providing and fixing RCC precast fencing pole near Fish farm at College of Fisheries Mangalore

Amount of Estimate : Rs. 247782.46

Notification No.:

Last date for submission :

Name of Contractor :

No. of items: 05 (Five items only)

Sl. No	Particulars	Qty	Unit	Rate as per SR	Amount	Rate quoted by contractor in figures and words	Amount
1	Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. Ordinary soil	13.37	Cum	273.90	3662.04		
2	Providing and fixing RCC precast fencing pole of size 0.15m x 0.15m x 2.0m casted in CC 1:1.5:3 with 20mm downsize aggregate making holes for drawing barbed wire at 30cm c/c using 10 mm dia vertical 4 TMT steel rods and 8mm dia stirrups at 15cm c/c fixed 1.5m above ground level using steel moulding, curing, transportation to work spot, fixing in plain cement concrete 1:2:4 using 20mm downsize aggregate including aligning to plumb and line, including cost of all materials, labour, hire charge of machineries lead, lift loading & unloading etc., Complete. (Excavation and PCC 1:2:4 has to be paid seperately) Market Rate Rs.750.00/-	110.00	Nos	750.00	82500.00		

No.of Corrections ()

No.of Over writing ()

Signature of Contractor


Professor and Head

3	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	12.00	Cum	6279.90	75358.80		
4	Providing barbed GI wire fencing of 12x12 gauge drawn into stone pillars or iron pillars including drawing in holes wherever necessary excluding the cost of pillars but including the cost of barbed wire and binding wire etc., including cost of materials, labour, HOM complete as per specifications.	1683.00	Rmt	34.10	57390.30		
5	Providing white washing to new wall surface in two coats with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.	176.00	Sqm	13.20	2323.20		

Total Rs. 221234.34


GST12% 26548.12

G.Total Rs. 247782.46

No.of Corrections ()

No.of Over writing ()

Signature of Contractor


Professor and Head