

KARNATAKA VETERINARY, ANIMAL AND FISHERIES SCIENCES UNIVERSITY, BIDAR
COLLEGE OF FISHERIES, MANGALURU-575002

No.FCM/EB/Interlock/2021-22(6)

Date: 01/12/2021

QUOTATION ENQUIRY

Sub: Quotation towards providing and Laying heavy duty cobble stones interlock pavers & construction steps near entrance of Animal House laboratory at College of Fisheries, Mangaluru -Reg.


With reference to the above cited subject, sealed quotations are invited for the following work. The quotation should reach the undersigned on or before 15/12/2021.

Please refer **Schedule B** for detailed work description

Note:

1. Quotations received after last date and having description of the materials incomplete will not be entertained.
2. Quotations should be raised in favour of "**Dean, College of Fisheries, Mangaluru-575002**"
3. Write compulsory reference number and quotations last date on sealed covers.
4. Rates should be quoted in Indian currency per unit.
5. Details of tax etc. should be mentioned separately.
6. Lowest quotation rate would be accepted.
7. The total amount for all the above items will considered for calculation and placing order is subject to meeting all the above conditions.

Yours faithfully,


Dean (Fisheries)
College of Fisheries
Mangaluru

Copy to:

- 1) Notice Board, College of Fisheries, Mangaluru
- 2) Notice Board, Technology wing, Hoige Bazar
- 3) Assistant Comptroller, COF, Mangaluru for kind information
- 4) College Website: www.cofm.edu.in

Schedule - B

Name of work : Providing and Laying heavy duty cobbles stones interlock pavers & construction steps near entrance of Animal House laboratory at College of Fisheries, Mangaluru

Amount of Estimate : Rs. 119364.20

Notification No.:

Last date for submission :

Name of Contractor :


No. of items: 5 (Five only)

Sl. No	Particulars	Qty	Unit	Rate as per SR	Amount	Rate quoted by contractor in figures and words	Amount
1	Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications.	4.25	Cum	273.90	1164.08		
2	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	1.41	Cum	6490.00	9150.90		

No. of Corrections ()

No. of Over writing ()

Signature of Contractor



Professor and Head

Professor and Head

Estate Branch In-Charge

College of Fisheries, Mangaluru - 575 002

3	Providing and constructing Lattrite size stone masonry in basement with cement mortar 1:6 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications.	6.46	Cum	5761.80	37221.23		
4	Providing 20mm thick cement plaster in single coat with cement mortar, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete as per specification.	53.80	Sqm	320.10	17221.38		
5	Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. heavy duty cobble stones 60mm thick	36.00	Sqm	1161.60	41817.60		

Total Rs. 106575.18
GST12% 12789.02
G.Total Rs. 119364.20

No.of Corrections ()

No.of Over writing ()

Signature of Contractor



Professor and Head
Professor and Head
Estate Branch In-Charge
College of Fisheries, Mangaluru - 575 007