## KARNATAKA VETERINARY, ANIMAL AND FISHERIES SCIENCES UNIVERSITY, BIDAR COLLEGE OF FISHERIES, MANGALURU-575002

No.FCM/EB/2020-21

Date: 18/03/2021

## **QUOTATION ENQUIRY**

Sub: Quotation towards Renovation of Laboratory at FRM Department, College of Fisheries, Mangalore- Reg.

With reference to the above cited subject, sealed quotations are invited for the following work. The quotation should reach the undersigned on or before 24/03/2021.

Sl. No.	Description of Item	Qty
1.	Providing and Fixing 15 mm thick densified tegular edged eco friendly <b>light weight calcium silicate false ceiling tiles</b> of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanizing @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24 x 38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross 'T' of size 24 x 28 mm made out of 0.33 mm (minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form, a grid of 1200 x 600 mm and secondary cross 'T' of length 600 mm and size 24 x 28 mm made of 0.33 mm thick (minimum) sheet to be inter locked at middle of the 1200 x 600 mm panel to from grid of size 600 x 600 mm, resting on periphery walls / partitions on a Perimeter wall angle pre-coated steel of size (24 x 24 x 3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screwes at 230 mm intervals and laying 15 mm thick densifed edges calcium silicate ceiling tiles of approved texture in the grid, including cutting / making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25 x 35 x 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.80mm spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all T sections shall be pre-painted with polyster baked paint for all heights, as per specifications, drawings and as directed by Engineer-in-charge.	20.25 Sqm
2.	Providing Venyl flooring of approved quality and make, fixed on the top of existing flooring fixed with suitable adhesive, including cutting to the requied size and fixing etc., complete licluding cost of all materials, mortar, labour, curing etc., complete as per specification.	22.95 Sqm
3.	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications with primer	62.00 Sqm

4.	Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	14.54 Sqm
5.	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. With 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg/m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder of approved quality.	5.78 Sqm
6.	Removing of window shutters	7.00 Nos
7.	Supplying and fixing ceiling fan down rod of 1' length	1.00 No
8.	Supplying and fixing LED ceiling lights	2.00 Nos

## Note:

- 1. Quotations received after last date and having description of the materials incomplete will not be entertained.
- 2. Quotations should be raised in favour of "Dean, College of Fisheries, Mangaluru"
- 3. Write compulsory reference number and quotations last date on sealed covers.
- 4. Rates should be quoted in Indian currency per unit.
- 5. Details of tax etc. should be mentioned separately.
- 6. GST/ PAN/ TIN numbers should be mentioned in the quotation.
- 7. Lowest quotation rate would be accepted.
- 8. The total amount for all the above items will considered for calculation and placing order is subject to meeting all the above conditions.

Yours Faithfully.

DEANTHISHERES, Collegeson Findances Managaloge 2

Copy to:

- 1) Notice Board, College of Fisheries, Mangaluru,
- 2) Notice Board, Technology wing, Hoige Bazar
- 3) Assistant Comptroller, COF, Mangaluru for kind information
- 4) College Website: www.cofm.edu.in